

## **Balmer Lawrie & Co. Ltd.**

P-43, Hide Road Extn., G&L Division, Kolkata – 700 088

Phone : 2450-0140, Fax : 2449-8493

=====

Tender Enquiry No. : GLK/TE17/213

Date : 28.10.2017

Due Date : 11.11.2017 upto 15:00 hrs.:IST

### **Sub : Execution of miscellaneous repairing jobs at G&L-Kolkata**

Quotation is invited for the above jobs at our premises at P-43, Hide Road Extn., Kolkata – 700088. Details of jobs are mentioned in the attached Enclosure. Other terms & conditions are as under :

1. Payment : Within 30 days from the date of submission of duly certified bill.
2. The selection of L1 bidder will be on the basis of lowest landed cost quoted for the items mentioned in the attachment.
3. The bid of any tenderer may be rejected, if a conflict of interest between the bidder and the company is detected at any stage.
4. All statutory liabilities will be borne by the vendors for execution of the stipulated jobs.

Interested vendor may submit their quotation, in the above prescribed format, **in a sealed envelope** to Shri Asish Chakraborty, Officer (Human Resources), at the above address on or before 09.11.2017 upt 15.00 hrs. IST.

Details of Miscellaneous repairing jobs at G&L-Kolkata

SN	Details of Jobs	Qty	Rate	Total
1	Main Gate			
a	Opening out of wooden panel from its position then opening out of Damages Wooden Frame from its position then supplying, fitting and fixing of 3"x3" size 7'-0"x3'-6" sal wood frame with TiK Ply Fixiing and polishing the frame and refixing the wooden panel at its position with all complete	L.S.		
2	Doctor's Chamber			
a	Repairing of wooden frame work and fixing 6 mm Ply of size 7'-0"x7'-0" and 7'-0"x3'-0"	70 sqft.		
b	Repairing of the swing door with all complete	12 sqft.		
c	Painting of two coats of oil based primer and two coats of enamel paints	200 sqft.		
3	HR Conference Room			
a	Repairing of Damp Wall and Putty work at Damages wall	120 sft.		
b	Scrapping, cleaning the wall, ceiling then applying two coats, plastic emulsion paints on wall and ceiling	350 sft.		
4	HR Toilet			
	Opening out of damages marble partition and refixing two nos. of marble partition at same positin	l.s.		
5	Administrative Building			
a	Repairing of two nos. of chamber with sand cement mortar at Lintel Beam Position	l.s		
b	Scrapping, cleaning the wall and ceiling then applying one coat of cement primer and 2 coats of plastic paints on wall with putty work all complete	350 sft.		
c	Polishing at Admin. Building Ground Floor Main Gate both sides	l.s		
d	Polishing at Admin. Building Ground Floor Entrance	l.s		
6	HR Building			
a	Supplying Fitting and Fixing of Rain Water Pipe at outside portion of HR Building	l.s		
b	Chipping out of damages plaster and plastering the wall with sand cement mortar with Damp Proof Chemicals	70 sft.		
	GST %			
	Total			