



**Balmer Lawrie & Co Ltd** (बामर लॉरी एंड कंपनी लिमिटेड)

**(A Government of India Enterprise)** (भारत सरकार का एक उद्यम)

**Engineering & Projects** (इंजीनियरिंग और परियोजनाएं)

**21, Netaji Subhas Road** (21, नेताजी सुभाष रोड)

**Kolkata - 700 001** (कोलकाता – 700 001)

## **Interior work, Furnishing, Internal painting, Internal illumination and finishing work of Office Building for Central Warehouse**

**At**

**AMTZ Andhra Pradesh**

**Tender No. EP / AMTZ / CWH / INT / 09**

**PART – II (PRICED)**

**NOTES:**

- 1.0 Details of the items under this Schedule shall be read in conjunction with the corresponding Specifications, Drawings and other Tender Documents.
- 2.0 The work shall be carried out as per approved drawings, Specifications and the description of the items in this Schedule and/or Engineer's instructions. Drawings enclosed with these documents are only preliminary for giving some idea of the work involved.
- 3.0 Items of work provided in this Schedule but not covered in the Specifications shall be executed strictly as per instructions of the Engineer-In-Charge.
- 4.0 Unless specifically mentioned otherwise in the Contract, the Tenderer shall quote for the finished items and shall provide for the complete cost towards power, fuel, tools, tackles, equipment, Constructional Plant, Temporary Work, labour, materials, levies, taxes, transport, layout, re-pairs, rectification, maintenance till handing over, supervisions, colonies, shops, establishments, services, temporary roads, revenue expenses, contingencies, overheads, profits and all incidental items not specifically mentioned but reasonably implied and necessary to complete the work according to the contract.
- 5.0 The Quantities of the various items mentioned in the Schedule of Items are approximate and may vary up to any extent or be deleted altogether. The Contractor, in his own interest, should get an indication of the probable extent of the work to be executed under any particular item in this Schedule before undertaking any preliminary and enabling work or purchasing bought out components related to the work.
- 6.0 Rates shall be quoted both in figures and in words in clear legible writing. No over writing is allowed. All scoring and cancellations should be countersigned by the Tenderer. In case of illegibility, the interpretation of the Engineer-In-Charge shall be final. All entries shall be in English language.
- 7.0 Engineer's decision shall be final and binding on the Contractor regarding clarification of items in this Schedule with respect to the other sections of the Contract.
- 8.0 For extra items, rates shall be derived from similar item rates included in the schedule of work. Where there is no such similar item available in the schedule, rate shall be analyzed as follows:

Rate for extra item = Cost of material (a) + cost of labour inclusive of all necessary tools, tackles, equipment, machinery and consumable (b) required to carry out the work + 15% of (a+b) towards profit and overhead + taxes, duties etc.

**SCHEDULE OF WORK**

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
1	<b>MINERAL FIBRE BOARD CEILING</b>				
	Supplying and fixing of mineral fibre board (Prepainted) false ceiling system of Armstrong/USG or approved equivalent make with 38 mm Silhouette Steel angle and shadow wall moulding (Dune Microlook reveal edge size 600 x 600) Armstrong/USG or approved equivalent make silhouette grid quick hook suspension system having main tee 3600mm long x 44 mm web height x15 mm wide tee section with 6 mm central recess. The Main runner is to be fixed with 4 mm thick pre stretched G.I wire with soffit cleat & G.I plug inserted on the main roof to be fixed at 1200 mm c/c . The last hanger at the end of each main runner should not be greater than 600 mm from the adjacent wall. The Main runner will be at the distance of 1200 mm C/C , the 1200 mm x 44 mm x 15 mm wide cross tee sections, having an integrally formed hook nose with precise butt cut joint end is to be fit in between the main tee at a distance of 600 mm to make a module of 1200 mm x 600 mm. Another cross tee having an integrally formed hook nose with precise butt cut joint end of size 600 mm x 44 mm x 25 mm is to be fitted at 1200 mm sections parallel to Main tee at 600 mm centre to make a square grid of 600 mm x 600 mm . All base frame material should be made of doubled walled high quality galvanized steel.	30	Sqm		
	It should have a capping of material coated with baked polyester paint . The perimeter trim of size 15 mm x 24 mm white coloured secured at 450 mm C/C is to run all along the peripheral. Dune/classic lite micro look prepainted tiles of 15 mm thick (min) or thickness as specified by manufacturer, suitable for 600 mm x 600 mm to be placed on grid. The rate to also include cost of providing additional members required for A/C grills and light fixtures all complete as per manufacturer's specification , drawing & direction of Engineer in charge.				
2	<b>PLAIN GYPBOARD FALSE CEILING</b>				

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
	Providing and fixing suspended Gypboard false ceiling , including stepping on the ceiling ( as shown in the drawing) with G.I perimeter channels of size 0.55 mm thick having one flange of 20 mm and other flange of 30 mm and wed of 27 mm along the perimeter of ceiling, screw fixed to RCC/BW with nylon sleever @ 610 mm c/c then suspending G.I intermediate channels of size 45 mm 0.9 mm thk & two flanges of 15 mm each from soffit @ 1220 mm c/c with ceiling angle of width 25mm x 10 mm x 0,55 mm thk fixed to soffit with G.I cleat & steel expansion fastners. Ceiling section of 0.55 mm thk having knurled web of 51.5 mm & two flanges of 26 mm each with lips of 10.5 mm are then fixed to the intermediate channel with the help of connectin clips & in direction perpendicular to the intermediate channel @ 450 mm c/c .12.5 mm thk tapered edge gypboard confirming to IS 2095: 1982 of M/S Indian Gypsum is then screw fixed to ceiling section with 25mm drywall screws @ 230 mm c/c, jointing the board and finishing so as to have a flush look which incudes filling and finishing the tapered and square edges of the board with jointing compound , paper tape and two coats of primer suitable of gypboard ( as per recommended practices of India Gypsum)	120	Sqm		
	The rate to also include cost of making cut-outs of light fittings, trap doors, diffuser & fixing frame of perimeter channels of size 20 x 27 x 30 x 0.55 mm thk required for cutouts supported suitably etc. complete as per drawing & directions of Engineer-in-Charge. The False ceiling is to be erected in horizontal / curved / slope shape or any shape in different levels as shown in drawing. No extra cost is payable for difference in shape and levels. The measurement will be taken in horizontal linear measurement in flat shape.				

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
3	<b>DOUBLE SKIN FULL HEIGHT PARTITIONS</b>				
	Providing & fixing upto 89 mm thick DOUBLE SKIN PARTITIONS (including , 100 x 12 mm Teak wood skirting ) PARTLY GLAZED & PARTLY LAMINATED/FULLY LAMINATED. The laminated portion to be made with well seasoned Hard wood frame or aluminium hollow section with 75 mm x 50 mm batons placed at 600 mm c/c both ways 6 mm thk Marine ply (Greenply/Mayur Ply/ Century Ply/ Mars Ply approved equivalent) to be fixed on both sides of the frame and best quality 1 mm thick laminate ( Green lam / Century Mica /Merini/ Sunmica or approved equivalent) of approved make shade & texture to be pasted over the maine ply with fevicol. The glazed portion to be made with 75 mm x 50 mm Hollock wood batons frame @ spacing as directed, best quality 6.0 mm thk transparent or frosted Float Glass ( Modiguard Sain Gobain / Pilkington approved equivalent )	85	Sqm		
	to be fixed with decorative Teak wood moulding of size 50 mm x 25 mm with high gloss polishing including Melamine finish, grouting of frame work in RCC / Brick work etc. with all enabling works complete as per specifications & directions of Engineer-in charge The Rate to also include cost of additional frame work necessary to fix the partition to ceiling , applying preservative treatment to timber for rot & termite proofing, applying fire retardant paint on wooden surface, etc. finishing the exposed surface of timber with stained spirit polish with melamine finish.				

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
4	<b>LOW HEIGHT PARTITIONS</b>				
	Providing & fixing in position DOUBLE SKIN LOW HEIGHT PARTITIONS on floor consisting of 50 x50 mm well seasoned hard wood battons or aluminium hollow section placed at 600 mm c/c bothways, jointed rigidly with nails, screws etc. & fixed to the floor with metal clamps grouted to floor and providing and fixing 6 mm thick BWR plywood as per IS 303 of " Green ply / Century or approved equivalent make on both sides of the frame work and best quality 1 mm thick laminated sheet of " "Greenlam", "Formica" "Century Mica" Marine make of approved shade, design, & texture to be pasted over the plywood with fevicol SH etc. without nailing in approved patterns.Finally the partition will be provided with 100 x 12 mm Teak wood skirting and 75 mm x 12 mm Teak wood moulding at the top complete with high gloss polishing with Melamine finish, grouting of frame work in walls, floors, etc. with all enabling works complete as per drawing and direction of Engineer in charge. The rate to also include cost of applying preservative treatment of timber for rot & termite proofing (ASCU), finishing the exposed surfaces of timber with stained spirit polish to desired colour & melamine finish.	12	Sqm		
5	<b>WALL PANELLING WITH LAMINATED FINISH</b>				
	Providing PANELLING ON WALLS including corners of windows, columns, etc. consisting of frame work with 50 mm x 25 mm well seasoned hard wood or aluminium hollow section @ 600 c/c (approx.) both ways jointed rigidly with nails, screws etc. fixed to walls, columns etc. with wooden plugs fixed with cement mortar (1:3) and providing & fixing 6 mm . thk BWR plywood as per IS 303, Century/Greenply or approved equivalent on top of frame work and finishing with best quality 1 mm thick Laminate ( Greenlam, Century Mica, Marine, Formica) of approved shade & finish to be pasted over ply without nailing.	60	Sqm		

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
	Finally the paneling will be finished with 60 x 35 mm thk Teak wood corner moulding at the junction of ceiling and wall (in case of full height panelling) and 35 x 12 mm teak wood boarding on top ( in case of low height paneling) and fixing 100 mm x 12 mm thick Teak wood skirting . The rate to also include cost of applying preservative treatment of timber for rot & termite proofing (ASCU) and finishing the exposed surface of timber with stained spirit polish to the desired colour & melamine finish, provision of extra frame work as necessary for Teak wood skirting & making cut outs for electrical fittings all as per drawings, specifications & directions of the Engineer in charge.				
6	<b>WOODEN JAMB LINING</b>				
	Providing and fixing <b>wooden jamb lining</b> to the windows and doors using SAL wood frame out of 50 x 25 mm covered with 12 mm thick BWR plywood and laminate complete with 50 x 18 mm Teak wood moulding at periphery of window duly melamine polish etc. complete.				
	a) upto 300 mm width	35	RM		
7	<b>COMMERCIAL FLUSH DOOR SHUTTER</b>	8.5	Sqm		
	Providing & fixing in position in any floor 30 mm thick factory made FLUSH DOOR SHUTTERS of solid core type conforming to BIS 2202 1991 having both face panels of BWR PLY of approved make ( Greenply / Century / Mayur or approved equivalent make,) Alpro or approved equivalent) Boiling water proof bonding , kiln seasoned stiles, rails and core timber treated with preservative (Ascu), including the cost of 4" oxidised iron but hinges ( 4 nos on each leaf) preparation of surface by sand papering, applying wood filler / sealant on entire surface to achieve a smooth finish , with all labour & materials complete as per drawings, specifications and directions of Engineer in charge.				
8	<b>PROVIDING &amp; FIXING LAMINATE</b>				
	Providing and fixing 1.00 mm thick LAMINATE of approved shade finish and make ( GREENLAM / CenturyMica / Merino / Formica) on new/old surface, including the cost of preparation of surface, supplying and applying Fevicol or equivalent adhesive with all labour and material complete , as per specifications and directions of Engineer-in-charge.				
a)	On new surface of flush door shutter	17	Sqm		

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
9	<b>WOOD WORK</b>				
	Providing wood work in frames of doors , windows , clerestory windows and other frames , wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (cost of hold fast lugs or dash fastener shall be considered in this item)				
a	Second Class Teak Wood	0.15	Cum		
b	Sal Wood	0.1	Cum		
10	<b>LOW HEIGHT CABINET</b>				
	Providing, fitting and fixing of low height storage-cum-filing cabinet of 400 mm. depth made of 18mm thick Partical Board as specified for top, bottom, sides, shelves and hinged shutter, 6mm thick Partical Board as specified for rear, finished with 1mm thick laminate, factory made with PVC/wooden leaping fitted with hinges , Hettich/Hafelle locks & SS handle of Hettich/Hafelle make, complete in all respect as per drawing and direction of Engineer-in-charge.	18	Sqm		
11	<b>FULL HEIGHT CABINET</b>				
	Providing, fitting and fixing of full height storage-cum-filing cabinet of 500 mm. depth made of 18mm thick BWR plywood/Block board as specified for top, bottom, sides, shelves and hinged shutter, 6mm thick BWR plywood as specified for rear side. All expose surface to be , finished with 1mm thick laminate on shutter with PVC/wooden leaping fitted with hinges Hettich/Hafelle locks & SS handle of Hettich make, complete in all respect as per drawing and direction of Engineer in - charge.The cost includes french polish in side the cabinet / exposed edge etc.	8.2	Sqm		



Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
12	<b>VERTICAL BLIND</b>				
	VERTICAL BLIND : Supplying and fixing "LUXAFLEX / VISTA LEVELOR / MAC brand vertical blinds with 100 mm wide woven fabric coated blinds, mechanism housed in head rail 25 mm wide and 30 mm high extruded from aluminium and louvers to be hung on superior quality runners with attached stainless steel spacers to obtain over lapping of 15 mm between the louvers. The tilting operation shall be done with steel ball chain and gathering of louvers by using a nylon cord. The louvers shall carry a sheet weight at the bottom to keep the louvers in position. They are to be inter connected at the bottom by using a fancy nylon link chain complete as per manufacturer's specifications .	18	Sqm		
13	<b>CP BRASS DOOR STOPPER</b> of hanging type , double buffer with necessary screws etc. with all labor and materials complete as per directions of Engineer in charge.	4	Each		
14	Supplying and fixing Chromium plated brass <b>HARDWARE FITTINGS</b> of approved quality , make and colour to doors and window shutter with required number of screws, etc. with all labour and materials complete,as per manufacturer's recommendations, drawings, and direction of the Engineer in charge.				
a)	Tower bolt 300 mm x 10 mm (stainless steel)	4	Nos		
b)	D type handle 200mm (chromium plated)	4	Nos		
15	Providing and fixing in position <b>MORTICE LOCK</b> of approved make (Godrej / Ozone / Garnish) CP brass body, 6 lever, conforming to IS 2209 inclusive of pair of handles of pressure Die cast Zinc alloy , Satin Chromium finished, with necessary screws etc. with all labour and materials complete, as per drawings, specifications and direction of the Engineer -in charge.	4	Nos		
16	Providing and fixing IS : 3564 marked Aluminium extruded section body tubular type universal <b>HYDRAULIC DOOR CLOSER</b> with double speed adjustment with necessary accessories and screws etc.complete.make-GODREJ / HAFELE/HETTICH/ HEAVY DUTY	4	Each		

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
17	Providing and fixing in position <b>FRAMELESS GLASS DOOR</b> made with 12 mm thick clear toughened glass of Saint Gobain / Pilkington / Modiguard make fixed to floor and soffit of ceiling / false ceiling rigidly and at the centres wherever required in line and level with SS patch fittings, floor spring of Dorma or approved equivalent make. Finally the door will be finished with S. S door handle with locking arrangement of Ozone / Hettich/ Hafelle make with all enabling works complete as per drawing , specification and direction of the Engineer-in-charge.	4.5	Sqm		
18	Providing & Fixing <b>SOFT-BOARD</b> with fabric with T.W. Framing all around. (Approx size: 1200mm x 600mm), Basic rate of fabric : Rs 200 per RM	7	Sqm		
19	Providing & installing <b>POLYESTER INSULATING FILM</b> as specified below of M/S Garware polyester or approved equivalent ) on glasses of doors / partitions including thorough cleaning of glass surfaces, scaffolding etc. with all labour & materials complete as per manufacturer's specifications & direction of the Engineer-in-charge. Frosted film 1.5 mil .(25 micron)	25	Sqm		
20	<b>ACRYLIC EMULSION PAINT</b> : Supplying all materials preparing surface by sand papering, scrapping of old paint if required, applying plaster of paris punning or cement putty on new/old surface to achieve a smooth and even surface, painting two or more coats of superior quality Acrylic Emulsion paint ( Royale of M/s Asian paints) of approved shade on the wall/ceiling surface to give an even shade over a coat of cement primer of approved quality including the cost of scaffolding etc. complete as per , manufacturer's instruction and direction of the Engineer-in-charge.	300	Sqm		
21	Supplying and applying two or more coats of superior quality <b>SYNTHETIC ENAMEL PAINT</b> on wood/steel surface of aproved make ( LUXOL HI GLOSS of M/s Berge paints or aproved equivalent ) quality and shade, including preparation of surfaces by wire brushing sand papering , removal of all loose scales, dust and grease providing necessary primer coat on new surface , scaffolding upto any height with all labour and materials as pe the specification and direction of the Engineer-in-charge.	10	Sqm		
22	<b>CEILING TRAP DOOR</b>				
	Providing trap door by 6 mm th Ply with necessary frame work by aluminum channel	2	SqM		

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
23	<b>WOODEN PELMATE</b>				
	Providing & fixing in position wooden Pelmate of size 150 mm x 150 mm made of 18mm thick BWR Plywood jointed with fevicol & nails finished on top with 4mm thick decorative plywood veneer pasted over plywood with adhesive (Fevicol SH).finished with melamine polish. Finally all the edges of the plywood will be covered with 4mm thick Teak Wood Lipping finished with stained spirit polish. The cost also include cost of polishing the internal surface of the pelmate with stained spirit polish.	12	RM		
24	Supplying & placing in position <b>OFFICE TABLE</b> of size <b>1200 x 600 x 750 (HT)</b> . The table will be provided with one no metal computer keyboard pull out tray, one no drawer unit ( <b>400 x 450 x 675 mm</b> ) with castors contaning 2 stationery drawers & 1 no. filing drawer. The table top, sides, drawer front and sides, wordrobe shutter, to be made with 25 mm & 18 mm thick Particle Board with laminated finish of 1mm thick laminate of approved shade, factory made with PVC leaping. The rate to include the cost of all fittings and fixtures, the runner for drawer ,make Hettich /Hafelle , Drawer handle of approved type (hettich/Hafelle make) all complete with labour and material as per drawing and direction of Engineer-in-charge.	3	Nos		
25	Supplying & placing in position <b>OFFICE TABLE</b> of size <b>1800 x 900 x 750 (HT)</b> . The table will be provided with one no metal computer keyboard pull out tray, one no drawer unit ( <b>400 x 450 x 675 mm</b> ) with castors contaning 2 stationery drawers & 1 no. filing drawer, one side unit of size ( 900 x 450 x 750). The table top, sides, drawer front and sides, wordrobe shutter, to be made with 25 mm & 18 mm thick Particle Board with laminated finish of 1mm thick laminate of approved shade, factory made with PVC leaping. The rate to include the cost of all fittings and fixtures, the runner for drawer make Hettich/Hafelle ) Drawer lock make Hettich/hafelle , Drawer handle of approved type (hettich make) all complete with labour and material as per drawing and direction of Engineer-in-Charge.	1	Nos		
26	<b>WORK STATION FIXED TO LOW HEIGHT PARTITION</b>				

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
	Providing, fitting and fixing work station to low height partition, made of 25mm.thick Particle board finished with 1mm laminate, factory made with PVC leaping fitted to partition with timber beads, complete in all respect as per drawing and direction of the Engineer in charge. The rate to also include the cost of providing metal keyboard pullout tray, wire manager, additional plywood support with laminated finish at the free end of table top etc with all necessary hardware fittings of Hettich make.				
a	1500 x 1500 x 600 mm	2	Each		
b	3000 x 600 mm ( Linear) with 2 drawer units	2	Set		
c	1500 x 600 mm (Linear) with 1 drawer unit	2	Set		
d	4300 x 600 mm (Linear) with 4 drawer unit	1	Set		

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
27	<b>DRAWER UNIT :</b>				
	Providing low height Modular drawer unit on castors of size <b>400 mm x 450 mm x 675 mm (H)</b> . containing 2 stationery drawers & 1 no filing drawer, made of 18 mm. thick Particle Board finished with 1mm thick laminate factory made with PVC leaping. The rate to include the cost of all fittings & fixture, runner for drawers make Hettich/Hafelle), drawer lock Hettich/Hafelle handles of approved type, castors etc all as per drawing and direction of Engineer-in-charge.	3	Nos		
28	<b>Conference Table:</b> Supply and fixing of 8-seater table with top made up of 19mm thk ply with laminated (1mm thick) finish and PVC beading/ moulding all round. The works to include all hardware etc. of approved make. All exposed edges to have wooden lipping stained to match the desk and melamine finished. All the surfaces to be in laminated finish.	3.6	Sqm		
29	<b>Center Table :</b> The centre table should be of premium quality. It should be 0.95 cm thick float glass with high Quality teak wood framing / MS ERU high quality chrome plated framing. material should be used of relevant ISI specification. Approx. Size shall be - 900mm (W)x 550mm(D)x 425 mm (H) (min)	2	Nos		
30	Providing <b>white board</b> of good quality for conference room alongwith standard teakwood beading alround, to be fixed on the wall as per direction.	2	Sqm		
31	<b>Sofa set :</b> Supplying two and three seated artificial leather sofa sets of specified size and dimension. Seat rest ,back rest and side arms assembly consist of a fabricated inner frame assembly with moulded polyurethane foam having density = $40 \pm 2$ kg/cum which provides strength as well as comfort to the sofa. Design & specification of sofa to get approved by the Engineer-in-charge prior to supply.				
a)	Three seated sofa shall have overall size of 1800L x 740D x 740H mm of approved make	1	Nos		
b)	Two seated sofa shall have overall size of 1300L x 740D x 740H mm of approved make	1	Nos		
32	<b>Executive Chair</b>				

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
	Back Height - <b>High back with head rest</b> chair with height range 950mm - 1050mm Back Finish - Mesh back with lumbar support in PP frame Back Mesh Color - Black Seat Finish - PU foam seat upholstered in Fabric with height 495 mm-595mm, width 510mm, Depth 510mm. Seat Fabric Color - Black Seat Height Adjustment - Pneumatic Mechanism Type - Synchronized Tilt. Back Tilt Lock - Upright Position Back Tilt Tension - Adjustable Armrests Type - 1 D arm Base Type - Black Nylon with 50mm twin wheel castors - Minimum Warranty Period - 3 years. Design & specification of chair to get approved by the Engineer-in-charge prior to supply.	1	Nos		
33	<b>Chair for Officers, Visitors &amp; Conference Room</b>	26	Nos		
	Back Height - <b>Medium Back chair</b> with height range 950mm - 1050mm Back Finish - Mesh back with lumbar support in PP frame Back Mesh Color - Black Seat Finish - PU foam seat upholstered in Fabric with height 495 mm-595mm, width 510mm, Depth 510mm. Seat Fabric Color - Black Seat Height Adjustment - Pneumatic Mechanism Type - Synchronized Tilt. Back Tilt Lock - Upright Position Back Tilt Tension - Adjustable Armrests Type - 1 D arm Base Type - Black Nylon with 50mm twin wheel castors - Minimum Warranty Period - 3 years. Design & specification of chair to get approved by the Engineer-in-charge prior to supply.				
34	Supply of <b>plastic chair</b> of approved colour and style from Nilkamal, Supreme or approved equivalent	5	Nos		
	<b>SUB-TOTAL (PART- A)</b>				

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
<b>PART- B (AIR CONDITIONING WORK)</b>					
Sl. No.	Description of item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
1	Supply, installation, testing & commissioning of Split Type Air Conditioner of <b>1 TR 3 star inverter type split type air conditioner</b> with Copper Condenser and all necessary piping and accessories, voltage stabilizer and remote control , remote control holder & remote control batteries. The scope also covers followings: i)Supply and Fixing of heavy duty Powder Coated steel Stand for mounting outddor unit. ii) Supply of Single Phase 3 pin 16-20 amps plug top for powering the AC. iii)Making holes in brick wall/ false wall for taking out cooper pipe and drain pipe and and making it good with plaster/putty and then touch up painting. Approved Make: Daikin/Voltas/LG/SAMSUNG/HITACHI	Set	2		
2	Supply, installation, testing & commissioning of Split Type Air Conditioner of <b>1.5 TR 3 star inverter type split type air conditioner</b> with Copper Condenser and all necessary piping and accessories, voltage stabilizer and remote control , remote control holder & remote control batteries. The scope also covers followings: i)Supply and Fixing of heavy duty Powder Coated steel Stand for mounting outddor unit. ii) Supply of Single Phase 3 pin 16-20 amps plug top for powering the AC. iii)Making holes in brick wall/ false wall for taking out cooper pipe and drain pipe and and making it good with plaster/putty and then touch up painting. Approved Make: Daikin/Voltas/LG/SAMSUNG/HITACHI	Set	4		
3	Supply & installation of additional insulated copper pipe in excess of 5M (supplied along with unit) alongwith winding the pipe with tape. To be paid at actual.	RM	10		
4	Supply & installation of additional drain pipe in excess of 5M (supplied along with unit) alongwith winding the pipe with tape. To be paid at actual.	RM	10		
5	Supply & Installation of Pedestal fan of sweep dia 450 mm with 3 speed control. (Make: Havells/Bajaj/Crompton)	Nos	2		
6	Supply & laying of additional 3 core 2.5/4 sq. mm. PVC Insulated flexible Copper Cable in excess of standrad cable supplied with the unit. To be paid at actual.	RM	20		

Sl No.	Description of Item	Qty	Unit	Rate (in Rs)	Amount (in Rs)
7	Supply & laying of 6 Module Pop up Box Brushed Steel with flush mounted box along with 3 pin socket, switch, LAN & Telephone socket. (Make :Legrand/Honeywell)	Nos	2		
8	Supply & Laying of High Quality 15 Pin Male To Male 1.5 Meter VGA Cable For Projector	Mtr	10		
	<b>SUB-TOTAL (PART- B)</b>				
	<b>TOTAL (PART-A + PART-B)</b>				
	<b>Add GST @ 18%</b>				
	<b>GRAND TOTALincluding GST</b>				